



Containerized diesel driven Fi-Fi system

Dutch dredging contractor and marine services provider Boskalis has won the contract for a multi year charter of one of her Platform Supply Vessels (PSV) in the Middle-East. For this contract the vessel needed to be equipped with external fire fighting capability. For this project, Fischcon delivered a containerized diesel driven fire water pump set for semi-permanent mounting on the after deck, connected to two roof mounted fire water monitors, remote controlled from the bridge.

Project	Boskalis Constructor
Operator / End user	Boskalis Offshore Subsea Services (Europe)
Classification society	B.V.
Capacity	Lloyd's Register
Scope of supply	2400 m ³ /h @ 130 mwc
	One (1) containerized driven Fi-Fi system, comprising of:
	<ul style="list-style-type: none">• 1x Diesel driven fire water pump set (2400 m³/h)• 2x Remote controlled, electric fire water/foam monitor (1200 m³/h)• 1x Foam proportioning system• 1x Priming system• 1x Set of suction and discharge piping• 1x Bridge control panel• Factory acceptance test with commissioning activities

